

4900 Front Fold Planters: Dimensions & Weights

Feature/Option	12R 30	16R 30	24R 30
Width - Transport	12' 0"	12' 0"	12' 0"
Width - Planting	33' 4"	43' 4"	62' 5"
Length - Transport			
Conventional Hoppers	27' 7"	31' 9"	42' 2"
Bulk Fill	29' 5"	33' 5"	43' 8"
(add 2' 9" to total length for drawbar hitch; add 1' 2" to total length fo 2 pt hitch)			
Length - Planting			
Conventional Hoppers	17' 6"	20' 0"	27' 1"
Bulk Fill	19' 4"	21' 11"	28' 10"
(add 2' 9" to total length for drawbar hitch; add 1' 2" to total length fo 2 pt hitch)			
Height - Transport			
Conventional Hoppers	11' 0"	11' 1"	11' 4"
Bulk Fill	11' 7"	11' 9"	12' 0"
24R includes row markers, flip axle and fertilizer 12R and 16R incudes row markers and fertilizer			
Height - Planting (Bulk Fill Only)	8' 9"	8' 11"	9' 3"
Weight - Base Machine			
Conventional Hoppers (empty; includes 3.0 bu conventional boxes)	15,711 lbs. Row Unit Hoppers/Mechanical Meters 15,711 lbs. Row Unit Hoppers/Vacuum Meters	20,032 lbs. Row Unit Hoppers/Mechanical Meters 20,032 lbs. Row Unit Hoppers/Vacuum Meters	30,147 lbs.* Row Unit Hoppers/Mechanical Meters 30,147 lbs.* Row Unit Hoppers/Vacuum Meters
Bulk Fill (empty; does NOT include optional flip axle available on 24R)	17,070 lbs. Bulk Fill/Mechanical Meters 17,070 lbs. Bulk Fill/Vacuum Meters	21,490 lbs. Bulk Fill/Mechanical Meters 21,490 lbs. Bulk Fill/Vacuum Meters	31,525 lbs.* Bulk Fill/Mechanical Meters 31,525 lbs.* Bulk Fill/Vacuum Meters * add 165 lbs. for optional flip axle
Weight - Hitch (empty)	5,038 lbs. Row Unit Hoppers 5,260 lbs. Bulk Fill	7,141 lbs. Row Unit Hoppers 7,380 lbs. Bulk Fill	9,933 lbs.* Row Unit Hoppers 10,146 lbs.* Bulk Fill * hitch weight reduced by 1,500 lbs. with optional flip axle engaged (may vary with other installed options)